



Telephone : 26494881
Telefax : 26495964

KAMALA NEHRU COLLEGE
(University of Delhi)

AUGUST KRANTI MARG, NEW DELHI-110049

KNC/2014/ 448

August 16, 2014

M/s _____

New Delhi-1100

Subject: Short-Term Quotation Inviting Notice regarding Fabrication of insulated A.H.U. Room (Two Nos.) for Auditorium Air-conditioning.

Sirs,

Sealed item rates quotations are invited latest by 30/08/2014 for Fabrication of insulated A.H.U. Room (Two Nos.) for Auditorium Air-conditioning, for detail of work & other information mentioned in Annexure-1 (attached herewith).

In respect of above you are advised to visit the site before quoting your rates, within next three (03) days and quote your rates after viewing the site accordingly in attached performa.

The college reserves the right to reject any/all quotation/s without assigning any reason.

The sealed quotations must be reach to the Principal's Office before 1.00 pm on 30/08/2014 and the amount be mentioned in words & figure both. The purpose of quotation stated on top of the envelope.

Yours sincerely

Minoti Chatterjee
Dr. Minoti Chatterjee
Principal

Renovation of Auditorium, kamla nehru college.

new delhi

BOQ for Auditorium- AHU Civil Work**Fabrication Of Insulated AHU Room (Two Nos.) for Auditorium Air-conditioning**

S.No.	DESCRIPTION OF ITEMS	QTY	UNIT	RATE	AMOUNT
	Note:				
	All items shall be considered comprehensively as per relevant details and specifications in drawings and control book. All items shall include accessories, hardware, patch fittings, pivots, floor springs, locks and handles and all such material for infill and framing etc. or labour for providing, fixing, fabricating, finishing and commissioning at site as required. All Items shall be handed over painted/polished and finished to satisfaction of management. All polish shall be Matt PU as per approval.				
a)	All external Doors and windows shall have Silicon seal around frames & joints				
b)	All items as indicated shall be calculated as per finished elevation and fixed on site.				
c)	All hardware make and quality shall be approved by management prior to fixing.				
e)	Contractor shall indicate all brand and quality for rates specified.				
f)	All Door and window frames shall be fixed with HILTI door and window anchor fasteners to the masonry or rcc.				
g)	All dimensions shall be verified at site prior to execution.				
h)	Contractor shall furnish quantities and cost breakup of the individual parts of the items along with quotation. Shop drawings shall also be submitted during execution.				
i)	Architectural drawings showing elevation of doors and windows shall be issued by Architect. The contractor shall submit the fabrication drawing for approval to the Architect before fabrication.				
j)	All Architectural hardware items shall be specified by management (Hettich / Hafele) and quoted for accordingly. Only key card door locking hardware shall be supplied by management.				
1.00	Supply and laying of Brick on edge / 4.5" thickness brick wall (as required) with common burnt clay F.P.S. (non modular) brick of class designation 7.5 in cement mortar 1:3 (1 cement : 3 coarse sand) including 16mm thk cement plaster on both side of wall, superstructure above plinth level and upto floor five level.	825.00	sqft		
2.00	Supply & fixing of Cement Sheet for Roof of AHU Room with proper slope complete as required (Area 225 sqft)	420.00	sqft		

3.00	Supply and fixing of Puf Panels for insulating Walls and Roof from inside of AHU Room complete as required (Area approx 550 sq ft. for one room)	1100.00	sqft		
4.00	Supply Installation of MS square tube 22 G for Air-conditioning duct Support complete as required.	80.00	Rft		
5.00	Providing and fixing door shutter and chocket including all hardware fixture for ahu room. Width appx 900mm and height 1800 apx.	2.00	each		
	Total Amount				